

OHS Generic Risk Assessment - Mobile Plant / Equipment

Supported by point of activity dynamic risk assessments, RA1, RA2, RA3 and specific risk assessments RA4 (lift)

	Ref: OHS 6.1.2-01 LC-04	
1	Location/ Site Details: Various	
2	Activity: Generic Activity - Inspection of Mobile Plant and Equipment	
3	Persons At Risk (who might be harmed): Engineer Surveyors, Special Service Engineers, Specialist Engineers, Senior Operations Team Leaders, trainee Engineer Surveyors, contracted staff and others not employed by AEIS (i.e. client's staff, members of the public). Responsible Manager(s): All Technical Operations Managers, Chief Engineer, Principal Engineers, Specialist Engineers, Special Services Manager and HSQ Manager.	
4	Hazard(s) (Potential to cause harm) Workplace Transport and Mobile Plant - Vehicle, traffic and plant movements. - Interaction with mobile plant during inspection activities. Slips, Trips, Falls and Work at Height - Slips, trips and falls. - Fall from height. - Uneven ground conditions. - Excavations. - Subsidence and unstable surfaces. Manual Handling and Ergonomic Hazards - Cutting, crushing, straining and impacting injuries arising from handling lifting tackle and inspection equipment. Mechanical and Electrical Hazards - Mechanical hazards from plant and equipment. - Electrical hazards associated with inspected equipment. - Stored energy and unexpected movement of machinery. Environmental Conditions - Exposure to heat, cold, wind, rain and sunlight.	Control Measures Elimination - Do not commence the inspection where adequate controls cannot be implemented. - Raise concerns with the responsible person on site and, where necessary, leave the site and issue a suitably worded Plant Not Available notification. - Ensure examination areas are adequately cleaned and prepared before inspection commences. Substitution - Where manual handling presents unacceptable risk, use suitable mechanical lifting equipment rather than manual handling techniques where practicable. Engineering Controls - Use lifting equipment for heavy or awkward items. - Establish exclusion zones and cordons where required. - Ensure suitable barriers, segregation or control of the inspection area. - Ensure adequate lighting before commencing inspection.

OHS Generic Risk Assessment - Mobile Plant / Equipment

• Poor lighting conditions. Site Activity and Third-Party Hazards • Hazards arising from other activities taking place on site. • Inadequate or inappropriate client preparation of the work area. Inspection-Specific Hazards • Hazards directly associated with undertaking the inspection activity. • Restricted access, positioning or visibility issues during examination. Noise Exposure • Exposure to elevated noise levels from operating plant and equipment. Violence, Aggression and Personal Safety • Assaults, threats or aggressive behaviour from visitors, contractors, employees or members of the public. Working Alone • Working alone in remote or isolated locations. • Delayed assistance following an accident, injury or medical emergency. • Inability to summon help due to poor communication coverage. • Increased risk when inspecting unfamiliar environments. • Exposure to violence, aggression or confrontation whilst working alone. • Becoming trapped, incapacitated or stranded whilst undertaking inspection activities. • Fatigue, stress or reduced situational awareness resulting from prolonged lone working.	• Utilise appropriate access equipment when working at height. • Ensure a competent trained plant operator is provided by the client when plant operation is necessary to facilitate inspection. • Maintain physical segregation between pedestrians and moving plant wherever practicable. • Use designated walkways and crossing points. Administrative Controls - Competence and Training • Training and authorisation in accordance with SAFed SS01 – Recruitment, Training and Competency of Engineer Surveyors. • Successful completion of the SAFed Health & Safety Passport. • Periodic fit-for-work medical assessments and health surveillance. - Risk Assessment and Planning • Undertake a dynamic risk assessment on arrival and throughout the inspection in accordance with RA1. • Review and apply RA2 and RA3 where required. • Apply the Manual Handling Risk Assessment where relevant. • Apply Working at Height Risk Assessment OHS 6.1.2-01 G-01 where required. • Continuously review dynamic risk assessments throughout the activity. - Communication and Site Coordination • Consult with the client regarding site-specific hazards before commencing work.
---	---

OHS Generic Risk Assessment - Mobile Plant / Equipment

		• Report to the responsible person when entering and leaving site. • Complete site inductions and review emergency arrangements. • Observe and comply with client-specific safety requirements. • Maintain awareness of surrounding site activities and changing conditions. • Avoid positioning within plant blind spots. • Maintain eye contact or agreed communication methods with operators before approaching plant. - Safe Systems of Work • Apply relevant AEIS procedures, guidance and safe working practices. • Take account of plant movements and other ongoing activities during inspection activities. • Comply with site traffic management arrangements. • Do not operate client plant unless authorised, competent and confident to do so. • Verify equipment has been isolated before inspection where required. • Confirm hydraulic, pneumatic, electrical and stored energy sources have been rendered safe. • Follow site lock-off/tag-off procedures where applicable. - Lone Working Arrangements • Comply with the AEIS Lone Working Procedure and associated guidance. • Inform the appropriate contact of planned locations, expected arrival times and anticipated completion times.
--	--	--

OHS Generic Risk Assessment - Mobile Plant / Equipment

		• Maintain regular communication with appropriate site contacts throughout the working day. • Ensure a charged mobile phone or other suitable communication device is available before travelling to site. • Assess communication coverage during the dynamic risk assessment and implement alternative arrangements where coverage is poor. • Do not undertake high-risk activities alone where emergency assistance may be required. • Report any concerns relating to personal safety, site conditions or lone working arrangements before commencing the inspection. • Terminate the inspection and leave the site if personal safety cannot be adequately assured. • Escalate missed contact arrangements in accordance with the Lone Working Procedure. Emergency Preparedness • Ensure emergency contact details are readily available. • Be familiar with site emergency arrangements and access/egress routes. • Ensure first aid and emergency response arrangements are understood before commencing inspection activities. Personal Protective Equipment (PPE) • Wear PPE and protective clothing appropriate to: ○ The inspection activity. ○ Site-specific requirements. ○ Environmental conditions. ○ Mechanical, electrical and noise hazards identified
--	--	--

OHS Generic Risk Assessment - Mobile Plant / Equipment

		during the risk assessment.
5	Potential Outcome: 5: Fatality or life changing injury	Probability/Severity: AEIS Employees: 3 moderate x 5 very high Others: 2 unlikely x 5 very high
6	Risk to others: 10: Medium	Risk to AEIS employees: 15: High
7	Re assessment after application of control measures	
8	Potential Outcome: 5: Fatality or life changing injury	Probability/Severity: AEIS Employees: 2 unlikely x 5 very high Others: 1 rare x 5 very high
9	Residual Risk to others: 5: Medium	Residual risk to AEIS employees: 10: Medium
10	Other useful information to be considered: General guidance on mobile work equipment can be found on the HSE web site: https://www.hse.gov.uk/work-equipment-machinery/mobile.htm	
11	Conclusion/ Recommendations: The risks associated with lone working are reduced to a low, tolerable level , provided that: • Controls are applied in accordance with the hierarchy of controls, and • Point-of-activity dynamic risk assessment is undertaken before and during the activity, and • Lone working is only undertaken where the task, environment, access arrangements and emergency response provisions remain suitable and sufficient. The activity is considered acceptable so far as is reasonably practicable with the stated controls in place.	
12	Reviews and further actions: Review at a maximum period of 12 months or sooner if: • Changes occur in equipment, environment or working practices • Incident, near miss, or health concerns are identified New information indicates the assessment is no longer suitable or sufficient.	

OHS Generic Risk Assessment - Mobile Plant / Equipment

Risk matrix to be applied to all tasks

Probability	5 (Almost certain)	5	10	15	20	25
	4 (Likely)	4	8	12	16	20
	3 (Moderate)	3	6	9	12	15
	2 (Unlikely)	2	4	6	8	10
	1 (Rare)	1	2	3	4	5
		1 (Very low)	2 (Low)	3 (Medium)	4 (High)	5 (Very high)
		Severity				

Probability of the event occurring:

- | | |
|--------------------|-------------------------------|
| 1. Rare: | Less than once every 10 years |
| 2. Unlikely: | Once every 5 to 10 years |
| 3. Moderate: | Every 1 to 5 years |
| 4. Likely: | Every 6 to 12 months |
| 5. Almost certain: | Every 1 to 6 months |

Severity of the event:

- | | |
|---------------|----------------------------------|
| 1. Very low: | Very minor injury |
| 2. Low: | Minor injury requiring first aid |
| 3. Medium: | Lost time injury |
| 4. High: | RIDDOR reportable injury |
| 5. Very high: | Fatality or life changing injury |

Ranking:

Green (1- 4):	Low risk
Yellow (5 – 12):	Medium risk
Red (15 – 25):	High risk

End of Document